


ARCHWAY PARK

General arrangement

Date: 05 11 2015
 Drawing no: 10317.100T revA
 Issue: -
 Drawn by: EB
 Checked by: MB



Scale: 1:200 @ A2

BURNS + NICE
 70 Cowcross Street
 London EC1M 6EJ
 T. 020 7253 0808 F. 020 7253 0909
 bn@burnsnice.com

- KEY**
- 1 Sports area - see 10317.201T
 - 2 Access steps - see 10317.212T
 - 3 Fence - see 10317.200T
 - 4 Goal/hoop combination - see 10317.300T
 - 5 Table tennis - see 10317.305T
 - 6 5m high slide - see 10317.306T
 - 7 Sleeper steps with rope railing - see 10317.203T
 - 8 Play house with toddler slide - see 10317.302T
 - 9 Accessible turn table - see 10317.303T
 - 10 Climbing frame - see 10317.301T
 - 11 Childrens swings - see 10317.309T
 - 12 Toddler swing - see 10317.304T
 - 13 Stroking cat - see 10317.307T
 - 14 Stainless steel benches - see 10317.204T
 - 15 Retaining wall - see 10317.213T
 - 16 Boundary fence - see 10317.216T

- Site Boundary
- New grass, see 10317.201T
- Contour lines (500mm steps)
- Permeable tarmacadam surface see 10317.201T
- Wet pour safety surface see 10317.201T
- Rubber grass mats see drawing 10317.201T
- New tarmacadam or new wearing course see 10317.110T and 10317.201T
- Asphalt for 7.5 tonne loading see 10317.201T
- Pcc edging see 10317.202T
- Brick edging retained
- Proposed new fence see 10317.200T
- Proposed light column by LBI
- Proposed refurbished bin see drawing 10317.205T
- Proposed boundary fence see drawing 10317.216T
- Extent of proposed Geocell stabilisation

Rev	Description	Date
A	Slope angle altered, slide repositioned, ramp access removed, sleeper steps added to slide, seats removed etc	05 08 2016
B	Boundary fence added, indicative only.	14 09 2016

- Notes:**
1. Copyright. The contents of this drawing may not be reproduced in whole or in part without the permission of BURNS + NICE.
 2. All dimensions to be checked by site measurement prior to the commencement of works or ordering of materials. Do not scale from this drawing.
 3. Lighting, including all ducting, foundations, fixtures and fittings, cabling and connections to be carried out by LBI. Contractor to allow in programme for LBI access to site.
 4. All tree felling to be carried out by LBI. Contractor to allow in programme for LBI access to site.
 5. For setting out of safety surfacing wet pour depths see 10317.107T
 6. For plan of areas of proposed new asphalt and existing asphalt with new wearing course see drawing 10317.110T

